



Engineering cell
Delhi Technological University
Shahbad Daulatpur, Bawana Road, Delhi-110042

File No: DTU/Engg. Cell/002592/2018-19/Civil

Dated: 24-09-2019

NOTICE INVITING QUOTATION

The Executive Engineer, Engineering Cell DTU invites, on behalf of Delhi Technological University, sealed percentage rate quotations from Civil Contractors up to 3.00 PM on 01/10/2019 for the following works, which shall be opened at 03:30 PM on the same day. Schedule of work along with terms and conditions can be obtained from office of the Executive Engineer or DTU website on all working days by submitting an application along with a copy of G.S.T. No. and PAN Card up to 03:00 PM on 01/10/2019.

S. No.	Name of Work	Estimated Cost (Rs.)	Time Allowed	Last date of Receipt of Quotation
1.	Providing and fixing Aluminium Partition work in Controller of Examination Office at DTU main campus, Bawana Road.	2,39,156/-	07 days	01/10/2019


TERMS & CONDITIONS:-

1. The work shall be carried out as per CPWD specifications/manufacturer's specification.
2. The rates quoted should be inclusive of all the taxes and duties & nothing extra shall be paid.
3. The quotations which are issued from the office of EE shall only be accepted, quotations in other forms shall be summarily rejected without assigning any reasons.
4. No T&P shall be issued to the firm by the department.

Enclosure: Schedule of work.

Copy to:-

1. Sr. Account Officer, DTU
2. AE (Civil)
3. DTU website
4. Notice Board



26/9/19
Executive Engineer
DTU Campus, Bawana Road
Delhi


Executive Engineer
DTU Campus, Bawana Road
Delhi


Schedule of Work

Name of work: **Providing and fixing Aluminium Partiton work in Controller of Examination Office at DTU main campus, Bawana Road.**

S. No.	Description of Items	Qty.	unit	Rate Rs.	Amount Rs.
1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) :				
1.1	For fixed portion Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	350.00	kg	355.20	124320.00
1.2	For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	30.00	kg	415.05	12451.50
2	Providing and fixing 12 mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of Engineer-in-charge. Pre-laminated particle board with decorative lamination on both sides	55.00	sqm	866.60	47663.00
3	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge. With float glass panes of 5.50 mm thickness	17.00	sqm	1003.95	17067.15
4	Providing and fixing of glass film or frosted film of superior quality (Garware or equivalent make) on glass panes to protect direct sun rays including scaffolding etc. all complete as per the direction of Engineer-In-Charge.	18.00	Sqm	607.00	10926.00
5	Taking out and Refixing aluminum partition after making necessary corrections to aluminium partitions etc complete as per direction of Engineer in charge	20.00	sqm	1097.52	21950.4
				Total	234378.05
				Add 12.75 cost index	29883.20
				Total	264261.25
				Less 9.50 % as per circular	-25104.82
				Total	239156.43
				Say:	239156.00


JE (C)


AE (C)


EE / DTU